



It should be noted that the suitability of the welded joint is defined by the joint integrity, as tested in accordance with CIRIA C735: 2014. This is most

commonly tested by air lance integrity testing to ASTM D4437-08: 2013. If the joint passes this test it is deemed acceptable in the verification process. In all cases it is recommended the installation of gas barrier geomembranes is completed by a suitably qualified and accredited installer (NVQ

L2/TWI/CSWIP or equivalent). Juta UK can offer advice as to the suitable/recommended installers.

All design decisions made by others that might have an impact on the gas and waterproof design performance should be brought to the attention of the design team and Juta UK Ltd. Final decisions and/or any recommendations should be approved by the design team and Juta UK Ltd.

Dimensions are not to be scaled from this drawing. All written measurements are to be checked on site by the contractor.

All rights described in chapter IV of the copyright, design and patents act 1988 have been generally asserted.

PD PF Not to Scale | Aug. 2020



MELTON GROVE WORKS BLACKPOOL ROAD LYTHAM FY8 5PL

Tel: 01772 754177