

CONCRETE
BLOCKWORK WALL

JUTA X8 CDM
(Cavity Drain Membrane)

JUTA LAP TAPE

JUTA DPC

JUTA CD PERIMETER DRAIN
IN MIN. 100 x 75mm RECESS.
CAN BE SAT IN 20mm
AGGREGATE IF REQUIRED.

JUTA CAB
Crystalline Active Barrier

DRAWING TITLE

JUTA CDM - INTERMEDIATE WALL

DRAWING NUMBER

JUTA.CDM.013

NOTES

- Detail is generic to application so should be used as a guide not a specific installation detail.
- JUTA Cavity Drain systems should be installed by suitably experience waterproofing contractors. Please contact JUTA for Specialist Contractors Details
- JUTA Perimeter Channels must be maintainable and installed to include minimum 1 outlet per 50l/m of perimeter channel. A minimum of 2 outlets must be provided as a minimum
- Cleaning ports / Jetting eyes must be provided to JUTA Perimeter Channel at every 12l/m or change in direction. For further detail see typical access port detail
- All new concrete surfaces must be treated with anti-lime coating to prevent leaching of free lime & mineral salts.
- All design decisions made by others that might have an impact on the gas and waterproof design performance should be brought to the attention of the design team and Juta UK Ltd. Final decisions and/or any recommendations should be approved by the design team and Juta UK Ltd.
- Dimensions are not to be scaled from this drawing. All written measurements are to be checked on site by the contractor.
- All rights described in chapter IV of the copyright, design and patents act 1988 have been generally asserted.

DRAWN BY

PD

CHECKED BY


PF

SCALE

Not to Scale

DATE

Nov 2019



MELTON GROVE WORKS
BLACKPOOL ROAD
LYTHAM
FY8 5PL

Tel: 01772 754177

JUTA
Adding the Future